

(Handwritten signature)

1. The completion period is 15 days (Fifteen days) from the date of issue of work order.
2. The Estimated cost of work is Rs.50451/- (Rupees Fifty thousand four hundred fifty one only)
3. Last date of submission of Quotation is 14.07.2023 at 15:00 hrs
4. Date of Opening of Quotation is 14.07.2023 at 15:30 hr or as decided by the convenor LPC.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, hiring of machinery like hydra for shifting, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. The Quantities shown are tentative and the quantity may increase or decrease with in permissible limits at the time of actual execution of work.
10. Payment shall be made as per the actual work done based on actual measurement at site.
11. All the materials used in the work shall be ISI marked.

Terms and Conditions:-

CUI invites quotation aluminium repair work of Boys Hostel Maheem Charan in Central University of Jammu. The work involves repair of Aluminium doors, fabrication of doors and ventilators. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUI resources.

Dear Sir,

Jammu.

Name of Work: Aluminium Repair Work in Boys Hostel Maheem Charan (Jmailpur) of Central University of

Sub: - Quotation.

.....
.....
.....

No: CUI/W/2023/364

Date: 11.07.2023




Rahya-Suchani (Bagla), District: Samba – 181143, Jammu (J&K)

Central University of Jammu
वर्मा केंद्रिय विद्यापीठम्
वर्मा-सूचनी (बागला), जिला सamba-181143, वर्मा (जम्मू एवं कश्मीर)

CC: Guard File
Notice Board

Encl: As Above

Executive Engineer
(Er. Vishal Bargotra)


11/11/2023

12. No advance payment will be made.
13. GST Bill should be provided.
14. CUJ reserves the right to cancel the work before the commencement of work and /or at any stage of execution as if found work is found substandard or not as per required specifications.
15. Payment shall be made through RTGS/NEFT.
16. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip
17. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.
18. Bidder may visit the site of place before quoting the rates and familiarise himself with the site conditions.
19. Bidders are required to submit following document along with Quotation:
 - i. Covering letter in Company letter head format.
 - ii. GST Registration/ Pan Card/Aadhar Card
 - iii. Contact Information of bidder (Complete address and Phone no.)

=====

Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

राहा-सुचानी (बागला), जिला सांभा-181143, जम्मू (जम्मू एवं कश्मीर)

Central University of Jammu

जम्मू केंद्रीय विश्वविद्यालय



जम्मू केंद्रीय विश्वविद्यालय

Central University of Jammu

राजा-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)

Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)



BOQ for Aluminium Repair work in Boys Hostel Maheen Charkan.

Sno	Item Description	Unit	Qty	Rate(Rs)	Amount(Rs)
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including clear angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.				
	For fixed portion using 18 gauge aluminium sections along with GI wire mesh	sqm	5.37	2800	15036
2	Providing and fixing Aluminium composite panel of 4mm thickness in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket, aluminium beading etc. complete as per the architectural drawings and the directions of Engineer-in-charge. The rate to include the cost of Aluminium sections of 18 gauge for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS:1285, fixing with dash fasteners of required dia and size, complete as per architectural drawings and the directions of Engineer-in-charge.	Sqm	4.9	4800	23520

MR

जम्मू केंद्रीय विश्वविद्यालय

Central University of Jammu

राजा-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)

Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)



3	Providing and fixing float glass of 4 mm thickness in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket, aluminium beadings etc. complete as per the architectural drawings and the directions of Engineer-in-charge. The rate to include the cost of Aluminium sections of 18 gauge for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS:1285, fixing with dash fasteners of required dia and size, complete as per architectural drawings and the directions of Engineer-in-charge.	sqm	2.31	4500	10395
4	Repair of Aluminium doors by removing, dismantling, cutting, assembling and refixing, etc.	no	3	500	1500
Total					50451

Rupees Fifty Thousand four Hundred fifty one only.(GST Inclusive)



Central University of Jammu

राया-सुचानी (बागल), जम्मू (जम्मू एवं कश्मीर)
राया-सुचानी (बागल), जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: Aluminium Repair Work in Boys Hostel Maheen Charakan of Central University of Jammu
Estimated Cost: Rs. 50451/- (Fifty Thousand four hundred and fifty one only) (Inclusive of GST)

Name of Work	Quote Percentage(Above/At Par/Below) on Estimated cost
Aluminium Repair Work in Boys Hostel Maheen Charakan of Central University of Jammu	In figures
	In words
50451/- (Fifty Thousand four hundred and fifty one only)	

Signature & Stamp of the vendor

